

Heavy Duty Thermal lamination size 15"



- 1). Thermal laminator with 2 hp ac variable speed drive with epicyclic speed reduction gear box.
- 2). **Feather touch** electric control panel comprising ('lg' vfi, overload relay), 10" electrical heated, super polished chromed laminating roller with ceramic heater immersed in (imported thermic fluid).
- 3). **Pid type temp. Control unit with digital display.**
- 4). **Motorized hydraulic** controlled lamination station (with pressure gauge).
- 5). Special **heat resistant elastomer counter pressure roller**, elevated thru hydraulic power pack, **with auto slide mechanism during power disruption.**
- 6). Duplex unwind stations with brake and film shifting mechanism.
- 7). Duplex rewinding station with heavy -duty felt-lined clutch.
- 8). Anodized aluminium feed table with new belt adjustment grooved roller.
- 9). **Photo-cell sensor for sheet feeding detection error,**
- 10). Carbon steel hobbled gears, dual shade powder tone finish.

This is an electronic message, hence signature not required.

Hyderabad

Pune

Vizag

Nairobi-kenya

TOTAL POWER: 7.5 HP -----(415v)

- a). 2 Hp Ac Motor 415 v; 50 Htrz.
- b). 'LG' VFI with display.
- c). 3Kw heater 415 v.
- d). Power Pack with 1 Hp. Motor.

MACHINE SPEED: 20 / 25 MTRS PER/ MIN FOR THERMAL LAMINATION.

If during the warranty, the buyer becomes aware of any defective material or faulty workmanship, then company on inspection, shall at its sole discretion, either repair or replace the defective part thereof.

Electrical, electronic, drives, motors, rubber, belts, hoses, hydraulic, pneumatic, glass and acrylic components/parts are not covered under this warranty. This warranty does not extend to any parts that have been submitted to misuse, negligence, accident, incorrect wiring, abuse modification, poor preventive maintenance or parts that are subject to damage due to voltage fluctuations or improper voltage. Our Liability is limited to replacement of defective parts or workmanship and does not cover any loss to customer, incidental or consequential

NOT IN OUR SCOPE OF SUPPLY: -

- Unloading, shifting, foundation of the machines and other masonry works.
- Electrical supply, incoming cables up to the control panel & all switch gears.
- All auxiliary equipment, utility plant, or ancillary machinery not mentioned in this quotation, such as *Fire Extinguishing equipment, etc.,*
- All materials required for test run at Seller's works (before delivery) at Buyer's works (After Delivery)

This is an electronic message, hence signature not required.

Hyderabad

Pune

Vizag

Nairobi-kenya